


CHAMBERSBURG SIGNALS

Mike Mudry, P.E., PTOE
MASITE Annual Meeting

9/29/2025


Overview

- » Project Background and Overview
- » Phase One (Section 100)
 - » Upgrades
 - » Construction Costs
- » Phase Two (Section 125)
 - » Upgrades
 - » ATSPM Case Study
 - » Construction Costs
- » What's Next
- » Q&A



Chambersburg Fun Facts?

- » Chambersburg is the only major Northern community burned by Confederate Forces during Civil War.
- » ChambersFest is held annually to commemorate this event.
- » Only municipality in PA operating electric, gas, water, and sanitary sewer utilities.
- » Largest municipal electric system in PA and the only one to own/operate electric generating plants.
- » County Seat of Franklin County.
- » Franklin County has its own MPO, supported by the Franklin County Planning Department.



Chambersburg Signals

- » Chambersburg owns 47 traffic signals.
- » Additional signals maintained by Chambersburg
 - » Guilford Township: 14 intersections
 - » Hamilton Township: 3 intersections
 - » Peters Township (Ft. Loudon): 1 intersection
- » Project signals NOT maintained by Chambersburg
 - » Greene Township: 2 intersections
- » TOTAL NUMBER OF INTERSECTIONS: 67
- » Major roadways – US 30, US 11, PA 316, I-81



Chambersburg Signals

» Phase One

- » SR 0011 Section 100
- » January 2018 – April 2022

» Phase Two


- » SR 0011 Section 125
- » August 2023 – December 2026
- » Currently under construction



Phase One Improvements

Signal Upgrades

- » 57 new cabinets with Econolite Cobalt controllers
- » 215 Wavetronix advance and stop bar detectors
- » Countdown ped signals at 13 intersections
 - » Downtown signals feature a mix of rest in walk (phase 2+6) and actuated all ped phases
- » 458 Backplates
- » 49 CCTV Cameras – Borough Intersections Only
- » Over 14 miles of new fiber, interconnecting 59 of the 67 intersections
- » Established communication with PennDOT via an existing T-1 line along I-81



Phase One Improvements

Design Decisions



- » No survey scoped; relied on existing permit plans, which presented challenges:
 - » Digitized existing permits into CADD
 - » Conducted ROW and Utility research (Susquehanna Civil)
 - » SUE Quality Level C (more like SUE QL C'ish)
- » Evaluated detection options and central monitoring systems
 - » Video vs Radar
 - » MAXVIEW vs Centrax



Phase One Improvements


Fiber Optic Layout

- » Multiple fiber optic rings and radial runs for redundancy
 - » Four separate fiber rings and one radial line
 - » One trunk line run between Borough and PennDOT
 - » CCTVs connected only to the Borough, not PennDOT
- » Retipping of existing fiber on Norland Avenue and Route 30 East of I-81 – 14 intersections
- » Managed Level 2 Ethernet switches




Phase One Fiber Layout



YELLOW RING



BROWN RING






PINK RING



Phase One Improvements

Borough Server House



Phase One Design Schedule/Clearances



- » Environmental/ROW/Utility Clearances
 - » No environmental impacts (BRPA)
 - » No ROW takes; Borough has numerous utility easements throughout project
 - » Utilities: Borough owned all the utility poles (except 4)

Phase One Construction Cost


- » Final Construction Estimate \$4.078 Million
- » Bids – Significant outlier!
 - » CM High \$3.114 Million
 - » Kuharchik \$4.050 Million
 - » Herr \$4,101 Million
- » The good – our estimate hit the median bid
- » The bad (but actually good) – The CM High bid was 1.5 standard deviations from the mean – a statistical outlier – WHY?
- » Minimal change orders: \$55,000
 - » Added 3 new controller boxes and added 2,000' fiber



Phase Two Improvements

Signal Upgrades

- » Limited to 59 intersections interconnected with fiber
- » Signal timing adjustments based on ATSPM data
- » Currently developing I-81 incident timing plans (DRIVE Engineering)
- » Safety review of existing signals
 - » Flashing Yellow Arrow (FYA) Upgrades
 - » Clearance time adjustments
 - » Replace 8" signals with 12" signals
- » Evaluate phasing and operations
 - » Add left turn phasing
 - » Add right turn overlaps



Phase Two Improvements

Design Decisions



- » Timing adjustments based on ATSPM data
 - » Overwhelming amount of data
 - » Decided to do spot counts using CCTV cameras
- » Incident management timing plans (DRIVE Engineering)
 - » Used RITIS data to identify actual incidents
 - » Correlated incidents on I-81 with ATSPM data anomalies to develop incident timings
 - » Began work after PS&E – will continue during construction and will be implemented in late 2026
- » Safety evaluation - review crash data to identify type of signal improvements that address crashes.
 - » FYA with peak hour protected-prohibited operation



Phase Two Improvements

ATSPM timing adjustments – Step 1


- » Verify intersection operation using remote front panel interface and Wavetronix software
- » Identify discrepancies and evaluated oversize pedestrian logic
- » Confirm vehicle detection and ped pushbutton operation
- » Evaluate ATSPM count data; radar counts varied +/- 30% in some locations – “we were spinning our wheels”
- » Decided to spot count using CCTV feeds and update Synchro Model



Phase Two Improvements

ATSPM timing adjustments – Step 2

- » Evaluate phase performance through split failure analysis
- » Evaluation criteria
 - » Split fail count and percentage (High value = insufficient green)
 - » Vehicle occupancy during green and red (assess queuing behavior)
 - » Interpretation
 - » High max out and split failure indicate a need more split time
 - » High gap out and low split failure indicate a potential split reduction



Phase Two Improvements

ATSPM timing adjustments – Step 3

- » Evaluate coordination and assess offsets to evaluate arrivals during green
 - » Platoon Ratio Calculation (Arrivals on Green/Green Time)
 - » Ratio > 1.15 is favorable (similar to HCM arrival type 4)
 - » Adjust offsets to improve platoon ratio

Arrival type	Range of platoon ratio (R_p)	Default value (R_p)	Progression quality
1	≤ 0.50	0.333	Very poor
2	$> 0.50 - 0.85$	0.667	Unfavorable
3	$> 0.85 - 1.15$	1.000	Random arrivals
4	$> 1.15 - 1.50$	1.222	Favorable
5	$> 1.50 - 2.00$	1.667	Highly favorable
6	> 2.00	2.000	Exceptional

Relationship between Arrival Type and Platoon Ratio (R_p) (Transportation Research Board 2000)




Phase Two Improvements

ATSPM timing adjustments

» Lessons Learned

- » Closely spaced intersections don't always require coordination
- » Oversaturated intersections may operate better with free operation and dynamic maxes.
- » Don't always need to avoid oversized peds, which can allow shorter cycle lengths
- » Don't be quick to assume anomalous data is due to an equipment malfunction – most likely due to an event.
 - » Could be an accident, illegally parked car, or trick-or-treaters
 - » CCTV footage was invaluable for identifying data anomalies






Phase Two Improvements

ATSPM Example – Wayne & Orchard


- » High-volume WB left turn movement without left turn phasing
- » Evaluate optimizing both splits and offsets at this intersection
- » Left turn phasing for EB and WB movements on Orchard will be incorporated as part of Phase 2 construction
- » As an interim improvement, used ATSPM data and spot counts from CCTV to improve traffic flow during peak hours



Peak Hours	Westbound			Eastbound		
	ThruRight	Left	Thru	ThruRight	Left	Thru
AM Peak: 11:45 AM to 12:45 PM	90	288	160	53	83	278
PM Peak: 4:15 PM to 5:15 PM	140	322	198	73	80	347


ATSPM Example – Wayne & Orchard

- » Phase 5 WB left turn split failures – controller frequently goes out of coordination due to oversized ped actuations.





ATSPM Example – Wayne & Orchard

- » After 5 iterations, new timing plans and offsets reduced split failures. During the afternoon (2:30-5:30 PM) split failures remain high. Increased cycle length from 90 to 105 seconds to prevent oversized ped calls from knocking signal out of coordination.



ATSPM Example – Wayne & Orchard

- » Purdue Coordination Diagram shows high percentage of vehicles arriving on green after implementing new timings.



Platoon Ratio

AM/Midday = 1.2

PM = 1.29

Favorable Progression

← More blue dots above green = arrival on green

← Below green line = arrival on red


Phase Two Design Schedule



- » Design Plans – limited to 28 intersections with equipment upgrades
 - » FYA
 - » Additional radar detectors at I-81/Route 30 intersection
 - » 12” signal heads
- » Timings continue to be implemented by TPD “on the fly”


Phase Two Construction Cost

- » Final Construction Estimate \$449,745
- » Bids
 - » B/M \$398,120
 - » Herr \$403,130
 - » Dixon \$404,670
 - » CM High \$427,000
 - » Kuharchik \$526,895
- » Mean bid price was \$431,963. TPD bid included 15% for mobilization/MPT. Low bid was 6%.
- » Final Design Phase for TPD/DRIVE will remain open through 2026 to allow additional timing updates preparation of as-build signal permits.



What's Next

- » After construction: re-evaluate signal timings with new FYA operations and phasing additions
- » Incident management timings: evaluate incidents on I-81 using RITS data and identify signals affected by diverted traffic; there are 3 exits along I-81 within the project area
- » Evaluate if the system will continue to operate on Econolite Centrax or migrate to new Kinetic Signals ATMS system
- » Long term: traffic volumes are relatively predictable; continue evaluating adaptive signal control
- » Short term operations – collaborate with Chambersburg to identify future monitoring of the system beyond 2026; consider applying for a Green Light Go grant for future monitoring.





Chambersburg Signals

SR 0011 Sections 100 and 125

QUESTIONS?

mmudry@TPDINC.com



www.TPDINC.com

